



Test Report : RSDW40H-12

40W 2"x1" Package Reliable Railway DC-DC Converter

■ DESIGN VERIFY TEST

Output Function Test

Input Function Test

Protection Function Test

Control Function Test

■ SAFETY TEST

Safety Test

■ RELIABILITY TEST

Environment Test

DESIGN VERIFY TEST

OUTPUT FUNCTION TEST

NO	TEST ITEM	SPECICATION	TEST CONDITION	RESULT
1	VOLTAGE ACCURACY	-1.0% ~ +1.0 % (Max)	I/P:110VDC O/P:FULL LOAD Ta:25°C	-0.48%
2	RIPPLE & NOISE	100 mVp-p (Max)	I/P:110VDC O/P:FULL LOAD Ta:25°C	55mV
3	LINE REGULATION	-0.2% ~ +0.2% (Max)	I/P:40VDC~160VDC O/P:FULL LOAD Ta:25°C	+0.02% ~ +0.08%
4	LOAD REGULATION	-0.5% ~ +0.5% (Max)	I/P:110VDC O/P:0% LOAD~FULL LOAD Ta:25°C	-0.09% ~ +0.12%

INPUT FUNCTION TEST

NO	TEST ITEM	SPECICATION	TEST CONDITION	RESULT
1	INPUT VOLTAGE RANGE	40VDC ~160 VDC	I/P:TESTING O/P:FULL LOAD Ta:25°C	34.9VDC ~160VDC
2	EFFICIENCY	89.0% (Typ)	I/P:110VDC O/P:FULL LOAD Ta:25°C	89.45%
3	DC CURRENT	0.5A / FULL LOAD (Max) 10 mA / NO LOAD (Max)	I/P:110VDC O/P:NO / FULL LOAD Ta:25°C	0.398A / FULL LOAD 5.6 mA / NO LOAD

PROTECTION FUNCTION TEST

NO	TEST ITEM	SPECICATION	TEST CONDITION	RESULT
1	SHORT PROTECTION	CONTINUOUS	I/P:160VDC O/P:FULL LOAD Ta:25°C	HICCUP MODE AUTO-RECOVER
2	OVER LOAD PROTECTION	125% ~ 210% (Typ)	I/P:110VDC O/P:TESTING Ta:25°C	158.72% HICCUP MODE AUTO-RECOVER

CONTROL FUNCTION TEST

NO	TEST ITEM	SPECICATION	TEST CONDITION	RESULT
1	REMOTE CONTROL	Power on : R.C. ~ - Vin>3.0~12Vdc or open circuit Power off : R.C. ~ - Vin <1.2Vdc or short	I/P:110VDC O/P:FULL LOAD Ta:25°C	Power on : R.C>3.0Vdc or Open Power off : R.C<1.2Vdc or short
2	TRIM CONTROL	+10%~-10% (Typ) Trim ~ +Vout Trim DOWN Trim ~ -Vout Trim UP Using 1.5M ohm VR	I/P:110VDC O/P:FULL LOAD Ta:25°C	Trim DOWN -10.3% Trim UP +9.5%

■ SAFETY TEST

SAFETY TEST

NO	TEST ITEM	SPECICATION	TEST CONDITION	RESULT
1	WITHSTAND VOLTAGE	I/P-O/P:3.0K VDC/min	I/P-O/P:3.0K VDC/min Ta:25°C	I/P-O/P: 0.002mA NO DAMAGE
2	ISOLATION RESISTANCE	I/P-O/P:500VDC>1000MΩ	I/P-O/P:500 VDC Ta:25°C	I/P-O/P>1000MΩ NO DAMAGE

■ RELIABILITY TEST

ENVIRONMENT TEST

NO	TEST ITEM	SPECICATION	TEST CONDITION	RESULT										
1	TEMPERATURE RISE TEST	1. ROOM AMBIENT BURN-IN : 8HRS I/P:110VDC O/P:FULL LOAD Ta=25°C 2. HIGH AMBIENT BURN-IN : 8HRS I/P:110VDC O/P:FULL LOAD Ta=50°C 3. HIGH AMBIENT BURN-IN : 8HRS I/P:110VDC O/P:50% LOAD Ta=70°C												
<table border="1" style="margin-left: auto; margin-right: auto;"> <thead> <tr> <th>NO</th> <th>Position</th> <th>1</th> <th>2</th> <th>3</th> </tr> </thead> <tbody> <tr> <td>1</td> <td>CASE</td> <td>70.2°C</td> <td>96.6°C</td> <td>101.6°C</td> </tr> </tbody> </table>					NO	Position	1	2	3	1	CASE	70.2°C	96.6°C	101.6°C
NO	Position	1	2	3										
1	CASE	70.2°C	96.6°C	101.6°C										
2	LOW TEMPERATURE TURN ON TEST	TURN ON AFTER 4 HOURS	I/P:110VDC O/P: FULL LOAD Ta= -40°C	TEST : OK										

OTHER

NO	TEST ITEM	SPECICATION	TEST CONDITION	RESULT
1	MTBF	MIL-HDBK-217F,GB,25°C TOTAL FAILURE RATE : 1.283 M.T.B.F : 779KHRS		

TEST RESULT	TESTER	APPROVAL
PASS	ARCHEN HSIAO	PETER CHENG